

SPAN & SHELTER

PRODUCT CATALOG
SPANANDSHELTER.COM

PRODUCT CATALOG

PARK & CAMP BUILDINGS


Standard buildings, packages & project spotlights

DESIGNED, PRICED & INSTALLED BY
SPAN & SHELTER
SHELTERS · BUILDINGS · BRIDGES

projects@spanandshelter.com
De Soto, Kansas


PARK &
CAMP

BUILDINGS



Cedar Forest Products offers a variety of timber wall buildings. Standard buildings are available, or CFP's design services can be used to match a structure to an organization's exact needs. CFP utilizes its Cedar Wall System for the Parkaire activity centers, park cabins, lodge buildings, and many other multi-use buildings. All wall components are preassembled and construction coded to assure a perfect fit, then dismantled and delivered to the job site. All structures include engineered drawings and installations instructions. Each building is designed for durability and years of comfort and service.



Spotlight

Franklin County- Louisburg, NC



Features

This spectacular Parkaire Activity Center 1 (PAC1) features a 6-post design, a covered picnic area, and two fully furnished restrooms.

About the Building

The shelter is located in Louisburg, NC. It was built in 2024.

Cedar Forest Products has many Park & Camp Buildings to choose from. Whatever the need, CFP has your project covered!

- Parkaire Buildings: Combined restroom and shelter
- Hexagon/Octagon Post & Beam Restroom: Restroom and shelter combined in a hexagon or octagon shape. Can also be fully enclosed.
- Traverse Bay Buildings: Configurable layouts with unlimited combinations
- Restroom Buildings: Sizable restroom buildings with unique exterior designs
- Lodge Buildings: Large timber buildings offering a variety of uses
- Cabins: 12 standard designs as well as custom designs available

Standard Features

Pre-Engineered Designs

- Each structure is pre-engineered to meet or exceed local building requirements
- Stamped & sealed drawings with calculations completed by a structural engineer to meet state & local building codes
- Restroom facilities meet ADA compliance requirements

Cedar Timbers

- Milled from Northern White Cedar for natural beauty, durability, and structural integrity
- Nominal solid 4" x 8" double tongue and groove timbers
- Disassembled and delivered to the construction site
- Cedar is highly desirable for its resistance to moisture, warpage, insects, and fungus that can shorten the service life of other wood buildings
- Cedar's cellular structure also offers a natural thermal efficiency

Exterior Wall Construction

- Predrilled starter holes for 10" coated screws speed construction of solid timbers
- Timbers are precut to length assuring staggered end joints and end matched for alignment, preassembled, and construction coded to ensure an easy field fit
- Disassembled and delivered to the construction site for reassembly
- Salem Square corners augment construction strength, reliability, and weather seal with a 6" timber screw
- Treated bottom plate with a sill seal and energy seal for all courses
- Trim package included for base, corners, and roofline

Roofing/Roofline

- #1 grade kiln dried 2" x 6" SYP roof decking
- 2" x 8" cedar fascia
- 30-year architectural asphalt shingle package
- Low pitch laminated SYP beams with Port Orford Cedar columns and 24" overhang

Doors & Windows

- Items are shipped to the job site ready for installation
- Primed steel doors with 3-part frame
- Standard hardware includes handles, locks, hinges, closer, and sweep

Interior Walls

- Interior walls use standard 2" x 4" construction
- Fiberglass Reinforced Panel (FRP) in the restroom areas for easy cleaning
- Multipurpose areas are finished onsite with provided 1" x 8" T & G prime or cedar
- Trim package included for base, corners, ceiling, doors, windows, and vents

PARK AND CAMP BUILDINGS

Optional Packages & Features

CFP offers plumbing and electrical fixture packages for all building kits. These packages provide the fixtures needed to complete the project. They do not include the piping, wiring, or conduit. MEP design plans are available for an additional charge. The packages need to be installed by a local plumbing or electrical contractor. HVAC can be added to buildings using a local HVAC contractor.

Plumbing Fixture Packages Included (plan dependent):

- Choice of stainless steel or vitreous china fixtures
- Floor mounted toilets and valves
- Urinals and valves
- Restroom toilet partitions
- Sinks with ADA shield
- Tankless water heaters
- Wall hydrant
- Grab bars
- Mirrors
- Toilet paper dispensers
- Paper towel dispensers
- Waste receptacles
- Sanitary disposal
- Soap dispenser
- Signs

Optional Fixture(s): Touchless valves, electric hand dryer, drinking fountain, baby changing station, wall mounted toilets, and bottle filling station







Electrical Fixture Packages Include (plan dependent):


- Light fixtures, bases, and lamps
- Outlets or GFCI outlets
- Junction boxes and switches
- Breaker boxes and breakers
- Overhead light sensors and controls





Optional Features

Color options and selections shown on page 74




























Tanglefoot

Tanglefoot Park utilizes a combination Rectangular Open Gable steel pavilion with T & G roof deck, Standing Seam metal roofing, and 4x8 double T & G Northern White Cedar timber wall infill. This stunning multi-use pavilion features insulated glass garage doors, restrooms, and catering kitchen.








The Market

Offering a large covered area, restrooms for visitors, and a spacious storage space, the Market is an impressive multi-use space. The facility is used for a Farmers' Market, community gathering place, party venue, and more.












Penfield

The versatile Penfield was engineered to serve the Air Force on its Northern Michigan base. Some of the many features include a front glass prow with large windows, a spacious activity center, kitchen, and complete restroom facilities.








Gateway Park


The 5,400 sq. ft. multipurpose facility at Gateway Park was designed to host numerous community events and markets, including a growers market. The building is equipped with restrooms, multiple roll up doors, and a serving kitchen. The facility allows for both a fully enclosed space as well as an open air feel with the roll up doors opened.



Robinson Preserve

An impressive custom Parkaire Activity Center (PAC) was created for Robinson Preserve to house their administration offices. The PAC building contains multiple office spaces, a restroom with shower, breakroom, and storage area. Abundant windows bring natural light into every workspace, creating a bright and welcoming environment for staff.








Tekesta Park

The Tekesta project is a multifunction, custom Parkaire Activity Center (PAC). The building offers a large storage area with double doors, two fully outfitted ADA compliant restrooms, and a small covered area. A perfect fit to any outdoor space.










Stephens County

Stephens County is a Traverse Bay (TBL) restroom building. TBLs utilize every inch for functionality. The building contains two fully outfitted ADA compliant restrooms and an outdoor drinking fountain. The exterior is finished with faux stone wainscotting and a Standing Seam metal roof.








Geist Waterfront Park

The Geist Waterfront Park project is a Split Gable Traverse Bay building made up of 6 modular units. The two tiers on the building are topped by a Standing Seam metal roof. The structure contains 8 fully outfitted family restrooms, a large storage area, and concession stand. Visitors will enjoy the natural sunlight pouring in from the multiple windows on the building clerestory.





Wood Color Options & Selections

Colors shown are only representative

29 Gauge Metal Roofing Color Options



Shingle Color Options



Stain Color Options

